

15-135-20246-00-00
WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ness County, Sec. 3 Twp. 19S Rge. (E) 25 (W)

Location as "NE/CNW/SW" or footage from lines G SE SE

Lease Owner Leben & McClure

Lease Name Schlegel Well No. 1

Office Address Box 486, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-11 19 69

Application for plugging filed 5-11- 19 69

Application for plugging approved 5-11 19 69

Plugging commenced 5-11 19 69

Plugging completed 5-11 19 69

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4443 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	404'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged with 70 sacks 50/50 Posmix cement @ 720'

Plugged with 20 saks cement @ 390'

Bridged Plug @ 40' with 10 sacks

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1969
CONSERVATION DIVISION
Wichita, Kansas
05-27-1969

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of May, 19 69

My commission expires April 1, 1971

Ulanda Nichols

Notary Public.

CORRECTED COPY

DRILLER'S LOG

COMPANY	Leben & McClure
CONTRACTOR	LEBEN DRILLING, INC.
FARM	SCHLEGEL #1
LOCATION	C SE SE SECTION 3-19S-25W NESS COUNTY, KANSAS
COMMENCED	4-30-69
COMPLETED	5-11-69

0	40	Surface Clay, Sand
40	404	Shale, Sand
404	460	Shale
460	1065	Shale, Red Bed, Sand
1065	1371	Shale, Sand
1371	1527	Lime, Shale
1527	1674	Red Bed
1674	2315	Shale
2315	2605	Lime, Shale
2605	3010	Lime
3010	3475	Lime, Shale
3475	3660	Shale, Lime
3660	3770	Lime, Shale
3770	4230	Lime
4230	4428	Lime, Chert
4428	4441	Mississippi
4441	4443	Lime, Chert
	<u>4443</u>	<u>RTD - D. & A.</u>

05-27-1969
 RECEIVED
 STATE CORPORATION COMMISSION
 MAY 27 1969
 CONSERVATION DIVISION
 Wichita, Kansas

8 5/8" 20# new surface casing set @ 404' cemented with 250 sacks Common cement, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Schlegel #1 Well, located C SE SE of Section 3, Township 19 South, Range 25 West, Ness County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 21st day of May, 1969.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1971