

15-135-22002-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY NESS SEC. 9 TWP. 19S RGE. 25W E/W
Location as in quarters or footage from lines:
SE NE

Locate Well
correctly on above
Section Platt.

Lease Owner KRM Petroleum Corp.
Lease Name STS Well No. 1-9
Office Address 817 17th St., Suite 820, Denver, CO 80202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed August 9, 1981
Application for plugging filed August 9, 1981
Plugging commenced August 9, 1981
Plugging completed August 9, 1981
Reason for abandonment of well or producing formation No commercial quantity of oil or gas encountered.
Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazar
Producing formation _____ Depth to top _____ bottom _____ T.D. 4620'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @ 1000' with 60 sx.

Set 2nd plug @ 700' with 40 sx.

Set 3rd plug @ 40' with 10 sx.

5 sx. in Rathole, 50-50 posmix, 4% gel, 2% c.c.

Plug was down @ 8:30 p.m., 8/09/81

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack L. Partridge, Vice Pres. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Jack L. Partridge

801 Union Center, Wichita, KS
(Address) 67202

SUBSCRIBED AND SWORN TO before me this 11th day of August, 19 81

My Commission expires: 7-13-85

Elizabeth G. Terry
Elizabeth G. Terry Notary
RECEIVED
STATE CORPORATION COMMISSION
AUG 18 1981
08-18-1981
CONSERVATION DIVISION
Wichita, Kansas



15-135-22002-00-00

CONTRACTORS WELL LOG

OPERATOR: KRM Petroleum Corp.
CONTRACTOR: Abercrombie Drilling, Inc.
WELL NAME: STS #1-9
LOCATION: SE NE, Sec. 9-19S-25W
Ness County, Kansas
SPUD DATE: 7/31/81
COMPLETION DATE: 8/09/81

0	1834	Sand & Shale
1834	1868	Anhydrite
1868	2262	Sand & Shale
2262	3386	Lime & Shale
3386	3705	Shale & Lime
3705	3773	Lime & Shale
3773	4048	Shale & Lime
4048	4309	Lime & Shale
4309	4413	Shale & Lime
4413	4603	Lime & Shale
4603	4620	Shale & Lime
	4620	Rotary Total Depth

Spud hole @ 1:00 p.m., 7/31/81. Drilled 755' of a 12 $\frac{1}{4}$ " hole. Ran 18 joints of 8 5/8" 24# casing set @ 750.75'. Cemented with 335 sx. of common 2% gel, 3% c.c. Cement did circulate. Plug was down @ 12:45 p.m., 8/01/81.

4620' TD. Set 1st plug @ 1000' with 60 sx. Set 2nd plug @ 700' with 40 sx. Set 3rd plug @ 40' Solid Bridge with 10 sx. 5 sx. in Rathole. 50-50 posmix, 4% gel, 2% c.c. Plug was down @ 8:30 p.m., 8/09/81.

SAMPLE TOPS:

Anhydrite 1835' - 1868'

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 14th day of August, 1981.

my commission expires 7-13-85

Elizabeth G. Terry
Elizabeth G. Terry
NOTARY PUBLIC
RECEIVED
STATE CORPORATION COMMISSION
AUG 18 1981
08-18-1981
CONSERVATION DIVISION
Wichita, Kansas

ELIZABETH G. TERRY
NOTARY PUBLIC
STATE OF KANSAS