

15-135-20621-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. BOX 17027
Wichita, Kansas 67217
NORTH

Ness County, Sec. 13 Twp. 19S Rge. 25W (X) (W)

Location as "NE/CNWESWK" or footage from lines C SW SE

Lease Owner Murfin Drilling Co.

Lease Name Gantz-Holloway Well No. 2

Office Address 617 Union Center - Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-1-72 19

Application for plugging filed 6-1-72 19

Application for plugging approved 6-1-72 19

Plugging commenced 6-1-72 19

Plugging completed 6-1-72 19

Reason for abandonment of well or producing formation

commercial quantities of oil not found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey - Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4418 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	483'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug at 510' w/ 70 sx. 50/50 pos, 6% gel.
Solid Bridge at 40' w/ 10 sx.

RECEIVED
STATE CORPORATION COMMISSION

14 1972
CONSERVATION DIVISION
Wichita, Kansas

06-14-1972

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rains & Williamson Oil Co., Inc.
Address 435 Page Court, 220 West Douglas, Wichita, Kansas 67202


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Wilson Rains, President of Rains & Williamson Oil Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
435 Page Court, 220 W. Douglas, Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 5th day of June, 1972

Juanita M. Green
Notary Public
Commission expires October 4, 1975



WELL LOG

15-135-20621-00-00

COMPANY Murfin Drilling Co.

SEC. 13 T. 19S R. 25W
LOC. C SW SE

FARM Gantz-Holloway NO. 2


RIG. NO. 3

COUNTY Ness
KANSAS

TOTAL DEPTH 4418

COMM. 5-22-72

COMP. 6-1-72



CONTRACTOR Rains & Williamson Oil Co., Inc.

CASINO

20	10	
15	8	5/8" @ 483' w/ 275 sx. common, 2% gel, 3%CC ELEVATION
12	6	
13	5	

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Clay and Sand	40
Shale	330
Shale and Sand	487
Shale and Shells	720
Shale	1100
Sand	1305
Shale	1411
Shale and Red Bed	1619
Anhydrite	1660
Shale	1858
Shale and Lime	2365
Shale and Lime	2550
Lime and Shale	2765
Lime and Shale	3305
Shale and Lime	3440
Lime and Shale	3790
Lime	4080
Lime and Shale	4165
Lime	4418
<u>Rotary Total Depth</u>	<u>4418</u>

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 14 1972
 CONSERVATION DIVISION
 Wichita, Kansas
 06-14-1972

State of Kansas)
 County of Sedgwick) ss:

I, Wilson Rains, President of the Rains & Williamson Oil Co., Inc. COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the Gantz-Holloway #2 well.

Wilson Rains
Wilson Rains



Subscribed and sworn to before me this 5th day of June 19 72

October 4, 1975

Juanita M. Green
NOTARY PUBLIC
Juanita M. Green