

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-20560-00-00

LEASE NAME Schroyer

WELL NUMBER #1

         Ft. from S Section Line

         Ft. from E Section Line  
C NE SE

SEC 10 TWP. 19S RGE. 25W (E) or (W)

COUNTY Ness

Date Well Completed         

Plugging Commenced 10-2-86

Plugging Completed 10-7-86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P.O. Box 21468 Tulsa, Oklahoma 74121-1468

PHONE # (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dodge City, Kansas

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4459'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	363'	none
				5-1/2"	4453'	2015'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.

Plugged off bottom with sand to 4150' and 5 sacks cement. Shot pipe @2531', 2105', pulled a total of 63 joints of 5-1/2" casing. Plugged surface with 2 hulls, 15 gel, 50 cement, 10 gel, 1 hull, 8-5/8" plug and 150 cement, 60/40 pos, 6% gel. Plugging (if additional description is necessary, use BACK of this form.) Complete.

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 12th day of November, 1986

Irene Hoover  
Notary Public

My Commission Expires:         



Form CP-4  
Revised 07-86

11-13-1986

15-135-20560-00-00

DRILLERS LOG

#1 Schroyer

CASING RECORD:  
357.30' of new 8-5/8"  
surface casing.

COMPANY: Patrick Petroleum Corporation

DESCRIPTION: NE 1/4  
Section 10-19S-25W  
Near E 180., Kansas

CONTRACTOR: Strata Drilling, Inc.

TOTAL DEPTH:  
4459'

COMMENCED: December 29, 1971

COMPLETED: January 10, 1972

SE  
NO. 135-20560-00-00  
9981 9  
09-05-1984

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Rock & Shale	0	40	Ran 357.30' of new 8-5/8" surface casing; set and cemented at 363.30' with 210 sacks of common cement, 2% gel and 3% C. C. Plug down at 11:00 P. M. December 30, 1971.
Shale, Sand	40	399	
Shale	399	419	
Shale w/Sand Streaks	419	825	
Red Bed, Shale & Shells with Sand Streaks	825	1083	
Anhydrite	1083	1117	
Red Bed & Shale	1117	1169	
Dakota Sand	1169	1438	
Red Bed, Sand & Shale	1438	1703	
#2 Anhydrite	1703	1738	
Shale, Rock, Red Bed w/ Lime Streaks	1738	2046	
Shale, Lime w/Broken Lime	2046	2534	
Lime & Shale	2534	3349	
Lime	3349	3460	
Lime & Shale	3460	3912	
Lime	3912	4299	
Lime & Shale	4299	4377	
Lime	4377	4401	
Cherty Lime	4401	4434	
Chert & Lime	4434	4443	
Lime	4443	4459	

ROTARY TOTAL DEPTH: 4459'

5 1/2" casing set and cemented at 4452' with 100 sacks of regular cement. Plug down at 12:30 P. M. January 10, 1972.

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

*Charles W. Steincamp*  
Charles W. Steincamp, President

Subscribed and sworn to before me this 11th day of January, 1972.

My Commission Expires:  
December 14, 1973

*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public

