

15-135-21499-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Ness County. Sec. 17 Twp. 19S Rge. (E) 25 (W)  
Location as "NE/CNWxSWx" or footage from lines C NE NW  
Lease Owner Chief Drilling Co., Inc.  
Lease Name Spruill Well No. #2  
Office Address 905 Century Plaza, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 16, 1978 19  
Application for plugging filed August 16, 1978 19  
Application for plugging approved August 16, 1978 19  
Plugging commenced August 16, 1978 19  
Plugging completed August 16, 1978 19  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4541 Feet  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	302'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged through drill pipe @ 550' w/70 sx. cement  
Plugged through drill pipe @ 240' w/20 sx. cement  
Plugged through drill pipe @ 40' w/10 sx. cement

RECEIVED  
STATE CORPORATION COMMISSION

AUG 25 1978

CONS. DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Chief Drilling Co., Inc.  
Address 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson  
905 Century Plaza, Wichita, Ks. 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of August, 19 78

MARILYN SINARD  
STATE NOTARY PUBLIC  
SEDGWICK COUNTY, KANSAS  
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard  
Marilyn Sinard Notary Public.

My commission expires \_\_\_\_\_

15-135-21499-00-00

WELL LOG

CHIEF DRILLING CO., INC.  
905 Century Plaza  
Wichita, Kansas 67202

#2 SPRUILL  
C NE NW Sec. 17-19S-25W  
Ness County, Kansas

CONTRACTOR: Warrior Drilling, Inc.  
CASING RECORD: 8 5/8" @ 302' w/185 sx.

COMMENCED: August 3, 1978  
COMPLETED: August 16, 1978

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATIONS</u>
Surface Sand	0	308	2517 Gr.
Sand & Shale	308	1224	2519 D.F.
Shale & Shell	1224	1731	2522 K.B.
Shale	1731	1798	
Anhydrite	1798	1838	
Shale	1838	3930	
Shale & lime	3930	4444	
Lime	4444	4541	
Total Depth	4541		

<u>FORMATION TOPS</u>	
Anhydrite	1798 + 724
Base Anhydrite	1838 + 684
Heebner	3863 - 1341
Toronto	3882 - 1360
Lansing	3903 - 1381
BKC	4230 - 1708
Ft. Scott	4417 - 1895
Miss.	4516 - 1994
RTD	4541 - 2019

D & A

RECEIVED

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

STATE OF KANSAS COMMISSION

08-25-1978  
AUG 25 1978

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C NE NW Sec. 17-19S-25W, Ness County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson, Vice-President

Subscribed and sworn to before me this 18th day of August, 1978.

MARILYN SINARD  
STATE NOTARY PUBLIC  
SEDGWICK COUNTY, KANSAS  
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard

Notary Public