


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Flat

Ness County, Sec. 17 Twp. 19 Rge. 25 (XX) (W)  
Location as "NE/CNWSWK" or footage from lines. SE SE NW  
Lease Owner. Hilton Drilling Company, Inc.  
Lease Name S & S Ranch Well No. 1  
Office Address 2421 Tenth Street, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 2, 1956  
Application for plugging filed August 9, 1956  
Application for plugging approved August 9, 1956  
Plugging commenced August 9, 1956  
Plugging completed August 13, 1956  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage  
Producing formation Depth to top Bottom Total Depth of Well 5000 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT
		0	239'	8-5/8"	239'	None
			4658	5-1/2"	4658'	3720'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back from 4588 to 4545' with rock, per State plugging orders.  
Dumped 5 sacks common cement with fillup at 4502'  
Loaded hole with fresh water. Pulled casing to 1070', mixed 25 sacks jell and circulated, pulled casing to 620', mixed 85 sacks common cement  
Strung in top of cement at 225', set rock bridge at 35', top of rock 27', mixed 9 sacks cement filled to bottom of cellar.

RECORDED  
INDEXED  
AUG 15 1956  
08-18-1956

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pawnee Drilling Company, Inc.  
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Henry Peacock, Secretary (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Henry Peacock*  
Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of August, 1956.  
*Mildred Hobbs*  
Notary Public.

My commission expires  
24-7368-8 3-53-20M

PLUGGING  
FILE SEC. 17 T. 19 R. 25W  
BOOK PAGE 88 LINE 16

DRILLER'S LOG

15-135-00128-00-00

COMPANY: Hilton Drilling Company, Inc. LOCATION: SE SE NW  
 Section 17-19S-25W  
 CONTRACTOR: Hilton Drilling Company, Inc. Ness County, Kansas  
 FARM NAME: S & S Ranch No. 1 Elevation: 2557' K. B.  
 COMMENCED: July 13, 1956 CASING USED:  
 8-5/8" set @ 239' w/ 200 sacks  
 COMPLETED: August 2, 1956 5-1/2" set @ 4622' w/ 150 sacks

Post Rock and Shale	130
Shale	655
Shale, Shells and Sand	930
Sand	970
Shale, Shells and Red Bed	1210
Lime	1225
Shale, Shells and Red Bed	1350
Shale and Sand	1380
Shale	1848
Anhydrite	1878
Shale and Shells	2505
Shale and Lime	2685
Lime	2955
Lime and Shale	3550
Lime	3635
Lime and Shale	3870
Lime	4402
Lime and Shale	4497
Lime	4510
Shale and Lime	4550
Sand, Chert and Shale	4556
Lime, Chert and Sand	4570
Lime, Shale and Chert	4600
Lime and Chert	5000
Total Depth	5000

08-18-1956

STATE OF KANSAS )  
 COUNTY OF BARTON) SS

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above-described.

HILTON DRILLING COMPANY, INC.

*Henry Pasch*  
 Secretary

Subscribed and sworn to before me this 3rd day of August, 1956.

*Mildred Hobbie*  
 Notary Public

MILDRED HOBBI  
 MY COMMISSION EXPIRES MARCH 6, 1958

**PLUGGING**  
 FILE SEC. 17 T. 19 R. 25W  
 BOOK PAGE 88 LINE 16