


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-138-30052-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County. Sec. 27 Twp. 19 Rge. 25 (E) W (W)
Location as "NE/CNW&SW&" or footage from lines C NE SE
Lease Owner Rains & Williamson Oil Company
Lease Name Fritzler Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 6-16-66 19
Plugging completed 6-21-66 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Depth to top Bottom Total Depth of Well 4515 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	469'	None
				5-1/2"	4504'	3591'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4515', sanded hole to 4490' and dumped 5 sacks of cement @ 4490' with dump bailer. Pulled 5 1/2" casing, bailed hole to 470', set rock bridge and dumped 25 sacks of cement. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (conservation division) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas

SUBSCRIBED AND SWORN TO before me this 30th day of June, 1966

My commission expires May 20, 1968
Milton J. Volin Notary Public.

2

ROTARY DRILLING LOG 15-135-30052-00-00

Operator: Rains & Williamson Oil Co.
No. 1 FRITZLER
C NE SE Section 27-19S-25W
Ness County, Kansas

Contractor: Rains & Williamson
Oil Co.

Commenced: 2-24-65

Rotary Released: 3-8-65

Remarks: Set 469.55' of 8-5/8"
surface casing with 240
sacks GL3 cement.

Set 4504' of 5-1/2" casing
with 150 sacks common cement.

FORMATIONS:

Surface Clay	45'
Shale	421'
Sand	438'
Shale	540'
Sand	560'
Shale	850'
Shale & Red Bed	940'
Red Bed & Sand Streaks	1095'
Anhydrite	1109'
D. Sand	1413'
Red Bed & Shale	1510'
Shale & Red Bed	1726'
Anhydrite	1776'
Shale	1965'
Shale & Shells	2165'
Shale & Lime Streaks	2345'
Shale & Lime	2355'
Lime & Shale	2505'
Lime	2820'
Shale & Lime	3590'
Lime & Shale-Chalk	3720'
Lime & Shale	3830'
Lime	4460'
Lime & Chert	4515'
Rotary Total Depth	4515'

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1966
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true
and correct to the best of our
knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State
of Kansas, County of Sedgwick, this 10th day of March, 1965.

My Commission Expires:
January 8, 1968

Shirley Keck
Shirley Keck, Notary Public