

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-62-3-117

API NUMBER 15-135-20,351-20409000 ^{KCC}

LEASE NAME Schlegel

WELL NUMBER #1

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 36 TWP. 19 RGE. 25 (E) or (W)

COUNTY Ness

Date Well Completed 2-2-1971

Plugging Commenced 12-23-97

Plugging Completed 12-23-97

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR L. D. Drilling, Inc

ADDRESS RR 1 Box 183 B Great Bend, Kansas 67530

PHONE#(316) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well oil well

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-23-97 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4426

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
surface		.0	608	8 5/8	608	none
Production			4415	5 1/2	4415	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set

Hooked to backside & mixed 15 sx. cement & pressured to 300#. Hooked to 5 1/2" csg. mixed 30 sx. w/200# hulls followed by 25 sx. gel spacer followed by 170 sx. and pressure to 500# Max. pressure 500# shut in 50# Total 215 sx. 65/35 8% gel 200# hulle

Name of Plugging Contractor Allied Cementing & L. D. Drilling License No. 6039

Address R.R. 1 Box 183 B Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. D. Drilling, Inc

STATE OF Kansas COUNTY OF Barton, ss.

Mike Kasselmann (Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct. God help me God.

STATE CORPORATION COMMISSION

(Signature) Mike Kasselmann

01-07-1998
JAN 7 1998

(Address) RR 1 Box 183 B Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 26 day of December, 19 97

STATE CORPORATION COMMISSION
 Wichita, Kansas

Bessie M. DeWerff
 Notary Public Bessie M DeWerff

My Commission Expires: 5-20-01



NOTARY PUBLIC - State of Kansas
 BESSIE M. DEWERFF
 My Appt. Exp. 5-20-01

15-135-20409-00-00

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

SCHLEGEL #1
C NW SE Section 36-19S-25W
Ness County, Kansas

Commenced: January 23, 1971
Completed: February 2, 1971

OPERATOR - George Reed

DEPTH		FORMATION	REMARKS
From	To		
0	495	Clay, rock, sand & shale	
495	610	Shale	Ran 15 joints 8-5/8" casing, set @ 608' w/350 sacks cement.
610	675	Sand & streaks of shale	
675	1110	Shale and redbed	
1110	1350	Sand	
1350	1634	Shale	
1634	1675	Anhydrite	
1675	2240	Shale	
2240	3600	Lime and shale	
3600	3809	Lime	
3809	4040	Lime and shale	
4040	4426	Lime	
4426	TD		Ran 137 joints 5-1/2" casing set @ 4415' w/50 sacks cement.

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the C NW SE Section 36-19S-25W, Ness County, Kansas to the best of my knowledge and belief.

James S. Sutton, II
James S. Sutton, II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 5th day of February, 1971, personally appeared James S. Sutton, II, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Barbara J. Layton
Barbara J. Layton, Notary Public

My Commission Expires February 1, 1972.



STATE OF KANSAS
JAN 7 1971
01-07-1998