

15-135-22082-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY NESS SEC. 36 TWP. 19S RGE. 25W E/W  
Location as in quarters or footage from lines:  
NW SW


Locate Well  
correctly on above  
Section Platt.

Lease Owner KRM Petroleum Corp.  
 Lease Name SCHLEGEL Well No. 1-36  
 Office Address 817 17th St., Suite 820, Denver, CO 80202  
 Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole  
 Date Well Completed August 19, 1981  
 Application for plugging filed August 19, 1981  
 Plugging commenced August 19, 1981  
 Plugging completed August 19, 1981  
 Reason for abandonment of well or producing formation No commercial quantity of oil or gas encountered.  
 Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? YES


Name of Conservation Agent who supervised plugging of this well Morris Lesslie  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4483'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set 1st plug @ 950' with 60 sx.  
Set 2nd plug @ 700' with 40 sx.  
Set 3rd plug @ 40' with 10 sx.  
10 sx. in Rathole. 50-50 posmix, 4% gel, 3% cement.  
Plug was down @ 7:00 p.m., 8/19/81.



(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Abercrombie Drilling, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Vice Pres. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Cntr., Wichita, KS 67202  
 (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of August, 19 81

My Commission expires: 7-13-85

Elizabeth G. Terry  
 Elizabeth G. Terry Notary Public



CONTRACTORS WELL LOG

15-135-22082-00-00

OPERATOR: KRM Petroleum Corp.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: SCHLEGEL #1-36  
 LOCATION: NW SW, Sec. 36-19S-25W  
 Ness County, Kansas  
 SPUD DATE: 8/11/81  
 COMPLETION DATE: 8/19/81

0	750	Surface Sand & Clay
750	1884	Sand & Shale
1884	2410	Sand, Shale & Red Beds
2410	2524	Shale & Sand
2524	2784	Sand & Shale
2784	3031	Shale & Lime
3031	3853	Lime & Shale
3853	4178	Shale & Lime
4178	4282	Lime & Shale
4282	4386	Shale & Lime
4386	4443	Lime & Shale
4443	4483	Shale & Lime
	4483	Rotary Total Depth

Spud hole @ 2:30 p.m., 8/11/81. Drilled 750' of a 12½" hole. Ran 18 jts. of 8 5/8" 24# casing set @ 746.65' and cemented with 200 sx. of Halliburton Lite, 150 sx. common 2% gel, 3% c.c. Cemented did circulate. Plug was down @ 6:00 a.m., 8/12/81.

4483' TD. Set 1st plug @ 950' with 60 sx. Set 2nd plug @ 700' with 40 sx. Set 3rd plug @ 40' Solid Bridge with 10 sx. 10 sx. in Rathbone. 50-50 posmix, 4% gel, 3% c.c. Plug was down @ 7:00 p.m., 8/19/81.

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the SCHLEGEL #1-36, NW SW, Sec. 36-19S-25W, Ness County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge  
 Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 25th day of August, 1981.

Elizabeth G. Terry  
 Elizabeth G. Terry  
 NOTARY PUBLIC

my commission expires 7-13-85

