

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 3293
Name: RUSSELL OIL, INC
Address 1: PO BOX 8050
Address 2: _____
City: EDMOND State: OK Zip: 73083 + _____
Contact Person: LEROY HOLT, III
Phone: (405) 752-7600
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 15-195-22786-00-00
Spot Description: _____
S2 NW, NW, NW Sec. 10 Twp. 11 S. R. 23 East West
570 Feet from North / South Line of Section
330 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: TREGO
Lease Name: BOLLIG N Well #: 1-10
Date Well Completed: 6/22/12
The plugging proposal was approved on: 6/21/12 (Date)
by: ED SHOEMAKER (KCC District Agent's Name)
Plugging Commenced: 6/22/12
Plugging Completed: 6/22/12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		SURFACE	8 5/8	263	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well with 230 sacks of 60/40 Poz, 4% gel, 1/4# Flo Seal, 1st plug @ 3936' with 25 sacks, 2nd plug @ 1767' with 25 sacks, 3rd plug @ 961' with 100 sacks, 4th plug @ 310' with 40 sacks, 5th plug @ 40' with 10 sacks, 30 sacks for Rat Hole, by Quality (ticket #879), plug was down @ 8:30am on 6.22.12.

Plugging Contractor License #: 33350 Name: SOUTHWIND DRILLING
Address 1: 8 NORTH MAIN Address 2: PO BOX 276
City: ELLINWOOD State: KANSAS Zip: 67526 + _____
Phone: (620) 564-3800
Name of Party Responsible for Plugging Fees: RUSSELL OIL, INC
State of KANSAS County, BARTON, ss.
JILL WAHLMEIER Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jill Wahlmeier

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
JUN 29 2012
KCC WICHITA



Southwind Drilling, Inc.
Plugging Orders & Reports

Lease: Bollig N 1-10

Plugging Received from KCC Representative:

Name: Ed Shaemaker Date: 6-21-12 Time: 6:45 PM

1 st plug @ <u>3936</u> feet, <u>25</u> sacks	Stands <u>63 1/2</u>
2 nd plug @ <u>1767</u> feet, <u>25</u> sacks	Stands <u>28 1/2</u>
3 rd plug @ <u>961</u> feet, <u>100</u> sacks	Stands <u>15 1/2</u>
4 th plug @ <u>310</u> feet, <u>40</u> sacks	Stands <u>5</u>
5 th plug @ <u>40</u> feet, <u>10</u> sacks	Stands <u>1 JT</u>

Mousehole: N/A sacks

Rathole: 30 sacks

Total Cement Used: 280 sacks

Type of cement: 60/40 P02 4% Gel 1/4" Floseal

Plug Down @ 6-22-12 @ 8:30 AM

Call KCC When Completed:

Name: Dave Wamun Date: 6-22-12 Time: 8:40 AM

RECEIVED
JUN 29 2012
KCC WICHITA