

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-035-20,866-0001

LEASE NAME J. D. GROOM

WELL NUMBER 1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

2970 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 33 TWP. 30S RGE. 5 (E) or (W)

COUNTY COWLEY

Date Well Completed 1975

Plugging Commenced 6-28-1990

Plugging Completed 6-28-1990

LEASE OPERATOR DAWSON-MARKWELL EXP

ADDRESS 3620 N.W. 58 OKLAHOMA CITY OKLAHOMA

PHONE (405) 947-2587 OPERATORS LICENSE NO. 5558

Character of Well S.W.D.

(Oil, Gas, D&A, ~~Oil~~, ~~Gas~~ S.W.D. Water Supply Well)

The plugging proposal was approved on 8-14-89 (date)

by MR. GLENN WARD (KCC District Agent's Name).

Is ACO-1 filled? YES If not, is well log attached? YES

Producing Formation MISSISSIPPI Depth to Top 2886' Bottom 2912' T.D. 2949-P.B.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
MISSISSIPPI	OIL	2886'	2912'	4 1/2	2970	NONE
				8 5/8	210	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

SANDED BOTTOM OFF FROM 2949-TO 2830'-BAILER DUMPED 5-SACKS CEMENT ON BOTTOM SET BRIDGE IN 4 1/2 AT 335' + ROCKED TO 325' RUN 300' 1" BETWEEN 2 5/8 & 4 1/2 & CIRCULATED CEMENT TO SURFACE PULLED 1" OUT CASING WAS DRY FILLED (CASING WITH CEMENT TO SURFACE WELD PLATE ON TOP
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor BUTLER CO DRILL CO License No. 6018

Address WINFIELD KANS STATE BANK BLDG

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Dawson-Markwell Exp

STATE OF OKLA COUNTY OF OKLA, ss.

Ed L. MARKWELL, JR. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 3620 N.W. 58 OKLA. CITY, OK

SUBSCRIBED AND SWORN TO before me this 9th day of July, 19 90

[Signature]
 Notary Public

My Commission Expires: 11/19/90

WELL LOG

15-035-20866-0000

Operator Dawson-Markwell Exploration Co.
 Comm _____ Comp _____
 Shot _____ Qts. From _____ ft. To _____ ft.
 Acidized _____ Gal. _____
 Prod. Formation _____
 Initial Prod. _____
 Elevation _____

Lease J.D.Groom Well No. 1
 Loc SE SW NW Sec 33 Twp 30S Rge 5E
 County Cowley State Kansas
 Contractor Triangle Drilling Co.

Casing Record			
Size	Ft.	Pulled	Remarks
8 5/8	148'	Cemented w/	110 sx.
5 1/2	2970	Cemented w/	125 sx.

FIGURES INDICATE BOTTOM OF FORMATION

0	-----	69	Surface Hole
69	-----	158	Shale and Lime
158	-----	325	Lime and Shale
325	-----	1795	Shale and Lime
1795	-----	2207	Shale
2207	-----	2245	Lime K.C.
2245	-----	2785	Lime and Shale
2785	-----	2915	Shale and Sand
2915	-----	2970	Lime Miss. R.T.D.

RECEIVED
 STATE CORPORATION COMMISSION

AUG 15 1963

CONSERVATION DIVISION
 Topeka, Kansas

15-035-20866-0001

**JOHNSON JET
SERVICE CO.**

Radioactivity Log

COMPANY WELL FIELD LOCATION COUNTY STATE	COMPANY: Dawson Maxwell Exploration	Well Location
	Oklahoma City Oklahoma	
	WELL: J.D. Groom #1	
	FIELD: Wilmont	
	LOCATION: SE-SW-NE Sec. 33-30S-5E	
	COUNTY: Cowley STATE: KANSAS	
	LOG ZERO: 5' A.G.L.	ELEV.
	DRLG. ZERO	ELEV.
	PERM. DATUM	ELEV.

TYPE OF LOG RUN NO. DATE TOTAL DEPTH (DRILLER) TOP OF LOGGED INTERVAL BOTTOM OF LOGGED INTERVAL TYPE OF FLUID IN HOLE FLUID LEVEL SOURCE STRENGTH & TYPE SOURCE SPACING - IN. LENGTH OF MEAS. DEVICE - IN. O.D. OF INSTRUMENT - IN. TIME CONSTANT - SECONDS LOGGING SPEED FT./MIN. RECORDED BY WITNESSED BY	GAMMA RAY - Neutron ONE 9-29-75 2949 1700 2947 Water AMBE 241 13" 1 1/4" 3 30 JOHNSON Dawson	RECEIVED STATE COMMISSION FROM LOG 1990 TO TO TO TO TO TO TO TO TO TO TO TO TO TO
--	---	---

WELL RECORD

RUN: 4.2 BIT SIZE: 10.2 CASING WT-LB: 10.2 FROM WELL RECORD: TO
 TO
 TO
 TO
 TO
 TO
 TO
 TO
 TO
 TO
 TO

STATE COMMISSION RECEIVED

TO CONSERVATION DIVISION
 Wichita, Kansas TO
 TO

2800

15035-20866-1001

2886
2 per. ft.
2899

2900

2912

Dawson Maxwell Exploration
J.D. Grook #1
Gowley County
SE 34-34
Sec. 33-305-52

T.D. 2949
0.51 L.O.L.
1 1/2" x 10.28 Casing
Elev. 1262 K.B.