

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH

	X		

Locate well correctly on above  
Section Plat

Marion County, Sec. 32 Twp. 17 Rge. 4 (E) NW SE NW

Location as "NE/CNWxSWx" or footage from lines \_\_\_\_\_  
Lease Owner Charles Omer  
Lease Name Stuchlik Well No. 2  
Office Address 6047 Howe Drive, Mission, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 8-10 1958  
Application for plugging filed 8-10 1962  
Application for plugging approved 8-13 1962  
Plugging commenced 8-16 1962  
Plugging completed 8-18 1962  
Reason for abandonment of well or producing formation low production

If a producing well is abandoned, date of last production July 31, 1961  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2479 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	152	none
				5 1/2	2397	1779.86

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled with sand to 2385 feet  
Dumped 4 sacks cement.  
Set 15 foot rock bridge 140 to 155 feet.  
Filled to surface with 2 1/4 yards ready mix cement

RECEIVED  
STATE CORPORATION COMMISSION

AUG 21 1962  
8-21-62  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Kent Well Servicing Co., Inc.  
Address Box 470, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.  
\_\_\_\_\_  
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Mary Payne

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 20th day of August, 1962

My commission expires April 14, 1966

Dale R. Daniel   
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company: JOHN GEHRKE  
Farm: Stuchlek

No. 2


SEC. 32 T. 17 R. 4E

N. SE NW

15-15-19259-0000

Total Depth. 2479'  
Comm. 7-29-58 Comp. 8-10-58  
Shot or Treated.  
Contractor. Slusser Drlg. Co.  
Issued. 11-22-58

County Marion  
KANSAS



Elevation 1173 RB

Production. 10 BOPD

CASING:

8 5/8" 152'  
5 1/2" 2397'

Figures Indicate Bottom of Formations.

surface soil	5
shale and shells	55
lime and shale	160
broken Lime	200
lime and shale	625
shale and lime	775
shale and shells	1150
shale and lime	1725
sand	1740
shale and lime	1845
lime	2135
lime and shale	2330
shale and lime	2394
chat	2397 RTD
chat	2411 Firm
chat	2417
chat	2428
chat	2436
chat	2443
chat and lime	2456
lime, hard	2471
lime and shale	2479
Total Depth	

Very slight show of Oil  
Slight Increase in Oil 2 EWP  
Increase in Water and Oil  
Increase in Water and Oil

TOP: SCOUT  
Mississippi 2394'

**RECEIVED**  
STATE CORPORATION COMMISSION

AUG 21 1962

CONSERVATION DIVISION  
Wichita Kansas