


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 9 Twp. 21 Rge. 13 (B) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NW SW
Lease Owner Petroleum, Inc.
Lease Name Harter 'B' Well No. 1
Office Address 100 Derby Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 20, 1951
Application for plugging filed November 20, 1951
Application for plugging approved November 20, 1951
Plugging commenced November 22, 1951
Plugging completed November 22, 1951
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3689 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	200'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged up to 200' and set wooden plug at
200'. Placed 15 sax cement on top of plug
(displaced through drill pipe). Placed
second plug at 35', and filled hole to
bottom of cellar with 10 sax cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Petroleum, Inc.
Address 100 Derby building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Eric H. Jager (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Eric H. Jager
100 Derby building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of November, 1951.

Charlotte Anderson
Notary Public.

My commission expires October 13, 1954

Handwritten notes and stamps at the bottom of the page, including a date stamp 'OCT 13 1954' and other illegible markings.

DRILLER'S LOG PARTER 'B' NO. 1

15-185-00718-0000

Petroleum, Inc., Lease Owner

Section 9, Twp. 21S, Rge. 13W

Garvey Oil, Contractor

Location: SW NW 8W

Drilling Commenced: November 12, 1951

County: Stafford

Drilling Completed: November 20, 1951

Production: D & A

Casing Record: 8 5/8" @ 200' w/175 sax

R.T.D.: 3689

Figures below indicate bottom of formation:

40 Surface soil & Sand
 95 Sand
 140 Chert & Sand Rock
 200 Shale & Shells
 255 Shale
 300 Sand
 779 Red Bed
 800A Anhydrite
 1515' Shale & Shells
 1625 Salt & Shale
 2385 Lime & Shale
 2855 Shale & Shells
 3145 Lime & Shale
 3200 Lime
 3268 Shale
 3362 Shale & Lime
 3349 Lime
 3558 Shale & Lime
 3644 Shale & Lime
 3689 Lime
 3689' R.T.D.

Tops:

Heebner: 3201 (-1303)
 Brown Lime: 3318 (-1420)
 Lansing: 3331 (-1433)
 Arbuckle: 3639 (-1741)

DST #1, 3640 $\frac{1}{2}$ -44, open 45 mins., rec. 7' mud, BHP 620 $\frac{1}{2}$

DST #2, 3642-49, open 1 hr., rec. 30' mud, 270 $\frac{1}{2}$ BHP.

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By Eric J. Jager

State of Kansas)
 County of Sedgwick) ss.

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 26th day of November, 1951.

PLUGGING
 FILE SEC 1 T2 R13W
 BOOK PAGE 24 LINE 24

Charlotte Hedman
 Notary Public

My commission expires: October 13, 1954