


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ness County. Sec. 7 Twp. 19S Rge. (E) 21W(W)
Location as "NE/CNW&SW&" or footage from lines C. NW. SE
Lease Owner Pickrell Drilling Company
Lease Name DeWald "C" Well No. 1
Office Address 705 4th National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 3, 19 65
Application for plugging filed October 3, 19 65
Application for plugging approved October 3, 19 65
Plugging commenced October 3, 19 65
Plugging completed October 3, 19 65
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4400 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	318'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 600', set plug, cemented with
20 sacks cement. Heavy mud to 240', set
plug, cemented with 20 sacks cement. Heavy
mud to 40'. Set plug. Cemented with 10 sacks
cement to bottom of cellar. Plugged rat hole with
2 sacks cement.

RECEIVED
OCT 13 1965
10-13-1965
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Building, Wichita 2, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

C. W. SEBITS (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebits
705 4th National Bank Building, Wichita 2, Ks.
(Address)

Subscribed and sworn to before me this 12th day of October, 19 65

My commission expires June 21, 1966
Maxine Blackman
Notary Public.



ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th National Bank Building
Wichita, Kansas

Rotary Drilling Commenced 9-22-65
Rotary Drilling Completed 10-3-65

LOCATION: DEWALD "C" No. 1, C NW SE Section 7-19S-21W, Ness County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: (15 jts) 8 5/8" surface casing set at 318', cemented with 175 sacks cement. Circulated. Completed 8:00 P.M. September 22, 1965. No oil run, D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

70	Top soil & Clay	<u>C. F. S.</u>
319	Shale & Shells	4248
700	Shale, shells & red bed	4258
895	Red beds	4285
1150	Sand	4322
1410	Shale, Shells & Red Beds	4330
1451	Shale & Shells	4334
1489	Anhydrite	4339
1640	Shale & Shells	4344
2065	Shale	
2575	Lime & Shale	<u>Slope Tests</u>
2690	Lime	2500
3305	Shale & Lime	3000
3460	Shale	3500
3545	Lime & Shale	4000
3700	Lime, Shale, Sandy	
3792	Lime & Shale	<u>S. L. M.</u>
4248	Lime	3583
4259	Shale & Sand	4106
4324	Lime & Shale	4298
4400	Mississippian - RTD	

RECEIVED
STATE CORPORATION COMMISSION
OCT 13 1965
10-13-1965

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company; that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. SEBITS, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF EDGWICK } ss.:

On the 13 day of October, 1965, before me the undersigned, a Notary Public, in and for the County of Edgwick State of Kansas, personally appeared C. W. SEBITS, to me known to be the Attorney-in-Fact who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact; he acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary Act and Deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public

