

15-135-20503-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ness County, Sec. 7 Twp. 19S Rge. 21W (E) (W)

Location as "NE/CNW&SW" or footage from lines c SW SE

Lease Owner Palomino Petroleum

Lease Name DeWald Well No. 1

Office Address 304 Insurance Bldg., Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 1 19 71

Application for plugging filed November 1 19 71

Application for plugging approved November 1 19 71

Plugging commenced November 1 19 71

Plugging completed November 1 19 71

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4377 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|------|--------|--------|------------|
| | | 0 | 295' | 8 5/8" | 295' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug: 550'/70 sacks cement
275'/20 sacks cement
40'/10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
NOV 9 1971
CONSERVATION DIVISION
Wichita, Kansas
11-09-1971

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hellar Drilling Company, Inc.

Address 339 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.

D. L. Hellar, President of Hellar Drlg. Co. Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. L. Hellar, President


339 Union Center Bldg., Wichita, Kansas 67202

(Address)

Subscribed and sworn to before me this 4th day of November, 19 71

My commission expires March 25, 1972.

Catherine Darcey
Catherine Darcey - Notary Public.



15-135-20503-00-00

DRILLER'S LOG

COMPANY: Palomino Petroleum, 304 Insurance Bldg., Wichita, Kansas 67202
 CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas 67202
 LEASE: #1 DeWald
 LOCATION: c SW SE 7-19S-21W, Ness County, Kansas
 COMMENCED: October 20, 1971
 COMPLETED: November 1, 1971
 CASING: Set 8 5/8" Surface Casing @ 295'/170 sacks cement

| | |
|-----------|------------------------|
| 0-100 | Clay and Rock |
| 100-295 | Shale |
| 295-810 | Shale & Red Bed & Sand |
| 810-900 | Red Bed |
| 900-1100 | Sand |
| 1100-1465 | Red Bed & Shale |
| 1465-1498 | Anhydrite |
| 1498-1545 | Red Bed & Shale |
| 1545-1930 | Shale & Shells |
| 1930-2320 | Salt Section & Shells |
| 2320-2495 | Shale & Shells |
| 2495-2515 | Shale & Lime |
| 2515-2740 | Lime & Shale |
| 2740-3090 | Shale & Lime |
| 3090-3480 | Lime & Shale |
| 3480-4280 | Lime |
| 4280-4325 | Shale - Lime & Chert |
| 4325-4342 | Lime |
| 4342-4377 | Miss. |
| 4377 | Rotary Total Depth |

RECEIVED
 STATE DEPARTMENT OF GEOLOGY
 NOV 12 1971
 CONSERVATION DIVISION
 WICHITA, KANSAS
 11-09-1971

D & A


STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 DeWald, located in c SW SE 7-19S-21W, Ness County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 4th day of November, 1971.



Catharine Darcey
 Notary Public - Catharine Darcey

My Commission Expires: March 25, 1972.