

15-135-30223-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
• Conservation Division
• State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Ness County, Sec. 7 Twp. 19 Rge. 21W (E) (W)

Location as "NE/CNWSW" or footage from lines C SE NW

Lease Owner Donald C. Slawson

Lease Name Goatley 'B'

Well No. 1

Office Address 408 One Twenty Building - Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 19, 1966

Application for plugging filed " 19, 1966

Application for plugging approved " 19, 1966


Plugging commenced " 19, 1966

Plugging completed " 19, 1966

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey - Box 582 - Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4406 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 540'; set plug; 30 sx cement

Mud to 320'; set plug; 20 sx cement

Set bridge at 40', cemented with 10 sx cement

2 sx in rat hole

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1966
09-30-1966
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.

Address 408 One Twenty Building - Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

DONALD C. SLAWSON

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

408 One Twenty Building-Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 1966

Ella Priess

Ella Priess

Notary Public.

My commission expires August 25, 1968

15-135-30223-00-00

WELL LOG

Company: Donald C. Slawson
 408 One Twenty Building
 Wichita, Kansas 67202

Farm: Goatley 'B' #1
 C SE NW of Section 7-19-21W
 Ness County, Kansas

Total Depth: 4406' Elevation: 2189 K.B.

Commenced: September 9, 1966

Completed: September 19, 1966

Contractor: Slawson Drilling Company, Inc.

Casing: 8 5/8" at 324' with 225 sx cement

0-30	Surface Clay
30-292	Lime Shells & Shale
292-1418	Shale & Shells
1418-1452	Anhydrite
1452-2160	Shale & Shells
2160-2170	Shale & Lime
2170-2725	Lime & Shale
2725-2950	Shale & Lime
2950-3091	Shale & Shells
3091-3409	Shale & Lime
3409-3601	Shale & Shells
3601-3654	Shale & Lime
3654-3999	Lime
3999-4119	Lime & Shale
4119-4241	Lime
4241-4300	Lime & Shale
4300-4383	Lime
4383-4406	Lime & Chert
4406	Total Depth


RECEIVED
 STATE CORPORATION COMMISSION
 SEP 30 1966
 09-30-1966
 CONSERVATION DIVISION
 WICHITA, KANSAS

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

I, Donald C. Slawson, of the Slawson Drilling Company, Inc., upon oath state that the above and foregoing is a true and correct copy of the log of the Goatley 'B' #1 well.


 DONALD C. SLAWSON

Subscribed and sworn to before me this 29th day of September, 1966.


 Ella Priess, Notary Public

My Commission Expires:
 August 25, 1968