

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-30201-00-00
Spot: SWSENE Sec/Twnshp/Rge: 23-20S-24W
1031 feet from N Section Line, 334 feet from E Section Line
Lease Name: PETERSILIE A Well #: 3
County: NESS Total Vertical Depth: 4365 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4300		WITH 2 SX CMT
PROD	5.5	4356	0	WITH 100 SX CMT
SURF	8.625	269		WITH 185 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/26/2012 8:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP 50' OFF BOTTOM WITH 2 SX CMT. PERFORATE @ ANHYDRITE & PUMP 50 SX CMT, THEN 80 SX CMT AT PERMIAN, THEN 50 SX CMT AT BOTTOM SURFACE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/26/2012 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4300' & 2 SX CMT. TEST CASING TO 500# & HELD. COULDN'T PULL CASING. PERFORATED AT 1760' & PUMP 50 SX COMMON W/3% CC. WAITED 1.5 HOURS & PRESSURED CASING TO 300# & HELD. PERFORATED AT 750' & PUMPED 175 SX CMT. DIDN'T CIRCULATE. MAXIMUM PRESSURE WAS 500#. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 500# & HELD. PULLED SWEDGE OFF CASING & PUMPED 30 SX CMT. 7/11/12: TOPPED OFF WITH 40 SX CMT. FLUID WAS DOWN 200'.

Perfs:

Top	Bot	Thru	Comments
4356	4365		

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL & COMMON CEMENT BY ALLIED.

Plugged through: CSG

District: 01

Signed Michael Maier
RECEIVED 7/26/12 (TECHNICIAN)
JUL 23 2012
KCC WICHITA

RECEIVED
JUL 18 2012
KCC DODGE CITY

Handwritten initials