

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21608-00-00
Spot: SENWSWNW Sec/Twnshp/Rge: 15-24S-20W
1750 feet from N Section Line, 450 feet from W Section Line
Lease Name: DOMME Well #: 1-15
County: EDWARDS Total Vertical Depth: 4908 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	388		WITH 300 SX CMT

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 07/14/2012 1:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JUAN TINOCO Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 4800' WITH 50 SX CMT. 2ND PLUG AT 1410' WITH 50 SX CMT. 3RD PLUG AT 410' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 07/15/2012 7:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

LOST CIRCULATION OF 1500 BBLS. 1ST PLUG AT 4800' WITH 50 SX 60/40 POZMIX 4% GEL 1/4# FLOSEAL. 2ND PLUG AT 1410' WITH 50 SX 60/40 POZMIX 4% GEL 1/4# FLOSEAL. WAIT 2 HOURS. 3RD PLUG AT 1410' WITH 100 SX CLASS A CMT W/2% CC 10% GYPSEAL 5% FLOSEAL. WAIT 4 HOURS. 4TH PLUG AT 1410' WITH 50 SX CLASS A CMT W/2% CC 10% GYP SEAL 5% FLOSEAL. WAIT 6 HOURS. 5TH PLUG AT 1410' WITH 50 SX CLASS A CMT W/2% CC 10% GYPSEAL 5% FLO SEAL. WAIT 6 HOURS. 6TH PLUG AT 1410' WITH 50 SX CLASS A CMT W/2% CC 10% GYPSEAL 5% FLO SEAL. WAIT 4 HOURS. HOLE STILL WOULD NOT LOAD. 7TH PLUG AT 385' SET CIBP INSIDE 8 5/8". 8TH PLUG AT 385' RAN DRILL PIPE TO PLUG & SPOTTED 50 SX CMT 60/40 POZMIX 4% GEL 1/4# FLOSEAL. 9TH PLUG AT 60' WITH 20 SX 60/40 POZMIX 4% GEL 1/4# FLO SEAL. 10TH PLUG TO CIRCULATE RAT HOLE WITH 20 SX 60/40 POZMIX 4% GEL 1/4# FLOSEAL. 11TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX 60/40 POZMIX 4% GEL 1/4# FLO SEAL.

Remarks: CEMENT BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
JUL 18 2012
KCC DODGE CITY

Signed Richard W. Lacey
7/20/12 (TECHNICIAN)

RECEIVED
JUL 23 2012
KCC WICHITA

Handwritten initials