

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20244-00-01
Spot: NWSW Sec/Twnshp/Rge: 14-29S-34W
1980 feet from S Section Line, 660 feet from W Section Line
Lease Name: STANTON Well #: 1-14
County: HASKELL Total Vertical Depth: 5600 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY, LLC
Address: 13727 NOEL RD STE 500
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4473		
CIBP		4500		WITH 2 SX CMT
PROD	4.5	5581	1865	WITH 350 SX CMT
SURF	8.625	1790		WITH 900 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/06/2012 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 4500' WITH 2 SX CMT. PLUG AT 1820' WITH 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: NONE
Date/Time Plugging Completed: 07/06/2012 4:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 4500' WITH 2 SX CMT. SHOT CASING AT 1988'. UNABLE TO POH W/CASING. RESHOT CASING AT 1865' & POH WITH CASING. 1ST PLUG AT 1820' WITH 80 SX CMT. 2ND PLUG AT 700' WITH 60 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4574	4584		KANSAS CITY

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
JUL 16 2012
KCC DODGE CITY

Signed

Jack MacLaskey
(TECHNICIAN)
7/16/12

RECEIVED

JUL 23 2012
KCC WICHITA

Form CP-2/3

ANT