

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-10210-00-02  
Spot: SWSWNW Sec/Twnshp/Rge: 7-27S-12W  
2992 feet from S Section Line, 4816 feet from E Section Line  
Lease Name: ICHU Well #: 18  
County: PRATT Total Vertical Depth: 4325 feet

Operator License No.: 31739  
Op Name: IUKA-CARMI DEVELOPMENT LLC  
Address: PO BOX 847  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3130		WITH 2 SX CMT
CIBP		3285		
CIBP		4074		
PROD	5.5	4265	0	WITH 125 SX CMT
SURF	8.625	401		WITH 150 SX CMT

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/27/2012 8:00 AM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Revd. from: GARELD INSLEE Company: IUKA-CARMI DEVELOPMENT Phone: (620) 770-0095

Proposed Plugging Method: CIBP @ 3130' WITH 2 SX CMT. PERFORATE 5 1/2" CASING AT 680'. CIRCULATE 5 1/2" X 8 5/8" ANNULUS WITH CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/13/2012 11:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3130' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PERFORATE 5 1/2" CASING AT 680'. PUMPED DOWN 5 1/2" CASING WITH 300 SX CMT. HAD GOOD RETURNS THROUGH OUT MOST OF JOB. RETURNS WENT TO POOR TO NONE. BEFORE LOSING CIRCULATION, HAD WATERY CMT COME AROUND. SHUT DOWN TO LET CMT SET. 6/29/12: TAG TOC @ 148 INSIDE 5 1/2" CASING & AT 81' INSIDE 5 1/2" X 8 5/8" ANNULUS. 7/13/12: RUN HOSE DOWN ANNULUS & CIRCULATE CMT TO SURFACE WITH 11 SX COMMON CMT. RUN HOSE IN 5 1/2" CASING TO 140' & CIRCULATE CMT TO SURFACE WITH 12 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4242	4252		
4014	4022		
3969	3975		
3829	3838		
3780	3784		
3769	3775		
3755	3763		
3155	3176		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA 10 YR RULE\*\* USED 60/40 POZMIX 4% GEL BY BASIC SERVICES.

Plugged through: CSG

District: 01

RECEIVED

JUL 17 2012

KCC DODGE CITY

Signed

RECEIVED

JUL 23 2012

KCC WICHITA

(TECHNICIAN)

Form CP-2/3