

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20365-00-00
Spot: E2E2W2NW Sec/Twnshp/Rge: 6-24S-17W
1320 feet from N Section Line, 1260 feet from W Section Line
Lease Name: HOAR Well #: 2-6
County: EDWARDS Total Vertical Depth: 4500 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4499	2050	WITH 150 SX CMT
SURF	8.625	256		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/05/2012 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: F.G. HOLL Phone: (620) 793-0915

Proposed Plugging Method: SAND PERFS & 5 SX CMT. PLUG AT 1240' WITH 15 SX GEL & 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: NONE
Date/Time Plugging Completed: 07/05/2012 11:15 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SANDED TO 4309' WITH 4 SX CMT. 1ST PLUG AT 1250' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4405	4406		

Remarks: **COMPLIANCE ISSUE: DENIED TA OBSTRUCTION IN CSG** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed

Jack MacClaskey
7/26/12 (TECHNICIAN)

RECEIVED

JUL 16 2012

KCC DODGE CITY

RECEIVED

JUL 23 2012

KCC WICHITA

Form CP-2/3

Handwritten initials