

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23756-00-00
Spot: NENESW Sec/Twnshp/Rge: 36-24S-13W
2310 feet from S Section Line, 2310 feet from W Section Line
Lease Name: HARRISON Well #: 36-23
County: STAFFORD Total Vertical Depth: 4225 feet

Operator License No.: 34110
Op Name: CAERUS KANSAS LLC
Address: 600 17TH ST, STE 1600 N
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	765		WITH 375 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/19/2012 12:00 AM
Plug Co. License No.: 34541 Plug Co. Name: NINNESCAH DRILLING LLC
Proposal Revd. from: RICK BARRIGER Company: NINNESCAH DRILLING LLC Phone: (620) 933-2001

Proposed Plugging Method: 1ST PLUG AT 4150' WITH 50 SX CMT. 2ND PLUG AT 790' WITH 50 SX CMT. 3RD PLUG AT 240' WITH 30 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 06/20/2012 12:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 4150' WITH 50 SX CMT. 2ND PLUG AT 790' WITH 50 SX CMT. 3RD PLUG AT 240' WITH 30 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: DP

District: 01

Signed

Eric MacLaren
7/26/12

(TECHNICIAN)

RECEIVED
JUL 17 2012
KCC DODGE CITY

RECEIVED
JUL 23 2012
KCC WICHITA

Form CP-2/3

Handwritten mark