

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-23387-00-00  
Spot: SESESE Sec/Twnshp/Rge: 22-14S-20W  
659 feet from S Section Line, 333 feet from E Section Line  
Lease Name: AUGIE BEFORT Well #: 22-164  
County: ELLIS Total Vertical Depth: 1377 feet

Operator License No.: 31828  
Op Name: STEWART, STEPHEN R. DBA AARON OIL  
Address: 1409 WASHINGTON CIR  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1200		
PROD	4.5	3805		175 SX
SURF	8.625	219		160 SX

Well Type: SWD UIC Docket No: D22260.0 Date/Time to Plug: 07/16/2012 9:00 AM  
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC  
Proposal Revd. from: TERRY W. PIESKER Company: DREILING OIL CO. Phone: (785) 735-4363

Proposed Plugging Method: Ordered 150 sx 60/40 pozmix 4% gel cement w/300 # hulls.  
PC 1435' w/175 sx cement.  
CIBP-1200'.  
Perforations- 3730'-3734', 3416'-3418', 3422'-3424' and 3432'-3434'.  
TD-3805'

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/16/2012 11:10 AM KCC Agent: PAT STAAB

Actual Plugging Report:

02/10/84 Well was plugged back to 1420'.  
Stewart Well Service drilled through CIBP to 1377' in hard cement.  
Ran in hole with tubing to 1345'. Mixed and pumped 85 sx cement w/150 # hulls to circulate cement to surface.  
Pulled tubing. Rigged to 4 1/2" casing with a swedge. Mixed and pumped 15 sx to pressure w/200 psi. Shut in pressure 200 psi.  
Rigged to 8 5/8" casing. Instant pressure.

Perfs:

Top	Bot	Thru	Comments
3730	3734		
3432	3434		
3422	3424		
3416	3418		

Remarks: QUALITY OILWELL CEMENTING TICKET # 914

Plugged through: TBG

RECEIVED

JUL 25 2012

KCC WICHITA

District: 04

Signed

(TECHNICIAN)

CM

Form CP-2/3

JUL 17 2012