

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23417-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 8-17S-11W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: WONDRA B Well #: 1
County: BARTON Total Vertical Depth: 3373 feet

Operator License No.: 30458
Op Name: RJM COMPANY
Address: PO BOX 256
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3072		150 SX
SURF	8.625	336		185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/12/2012 12:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CHRIS HOFFMAN Company: RJM CO Phone: (620) 587-3600

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/12/2012 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations. Topped w/5 sx cement.
Shot off casing at 1472'. Pulled casing to 1465'. Pumped 125 sx cement w/200 # hulls.
Pulled casing to 950'. Pumped 50 sx cement w/100 # hulls.
Pulled casing to 500'. Pumped 40 sx cement w/100 # hulls.
Pulled casing to 240'. Circulated cement w/70 sx cement.
Pulled casing. Hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3352	3356		ARBUCKLE
3086	3300		LANSING
3016	3026		DOUGLAS

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie
7/26/12 (TECHNICIAN)

CM

JUL 18 2012

Form CP-2/3

RECEIVED
JUL 25 2012
KCC WICHITA