

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19259-00-00
Spot: NESENE Sec/Twnshp/Rge: 32-15S-11W
3630 feet from S Section Line, 330 feet from E Section Line
Lease Name: BORELL B Well #: 5
County: RUSSELL Total Vertical Depth: 3320 feet

Operator License No.: 31086
Op Name: RICHLAN DRILLING, A GENERAL PAR
Address: 598 2ND AVE
BEAVER, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3310		150 SX
SURF	8.625	290		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/16/2012 1:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RICH SCHREIBER Company: RICHLAN DRILLING Phone: (620) 793-2032

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/16/2012 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 640' and 250'.
Problem well. Bad casing. Ran tubing to 640'. Hit bad spot in casing. Worked tubing. Got through bad spot. Tubing might have gotten outside casing. Stacked out with tubing at 1085'. Decided to plug.
Ran tubing to 1085'. Tied to tubing. Pumped 60 sx cement.
Pulled tubing to 600'. Pumped 145 sx cement. Cement circulated out of casing. Shut in casing. Circulated cement out surface pipe with 60 sx cement.
Pulled tubing. Tied to casing. Pumped 10 sx cement. Pressured to 500 psi. Shut in at 300 psi.

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG 1 1/2"

RECEIVED
JUL 25 2012
KCC WICHITA

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM