

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20668-00-00
Spot: SWNENWNW Sec/Twnshp/Rge: 24-3S-27W
610 feet from N Section Line, 970 feet from W Section Line
Lease Name: KINCAID Well #: 1-24
County: DECATUR Total Vertical Depth: 3800 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3799		150 SX
SURF	8.625	217		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/16/2012 11:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 269-7290

Proposed Plugging Method: 8 5/8" surface casing set @ 217' w/175 sx cement. 4 1/2" production casing set @ 3799' w/150 sx cement. Top of cement 2800'. Perforations: 3530'-3534', 3547'-3549', 3570'-3572', 3581'-3582', 3583'-3587', 3657'-3659', 3710'-3712' and 3714'-3716'. Arrow set 1x packer stuck in hole. Top of fish @ 3636'. Ordered 450 sx 60/40 pozmix 4% gel cement w/900 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/16/2012 2:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing @ 2182' and 1516'. Ran tubing to 3500'. Pumped 80 sx cement w no hulls and 80 sx cement w/300 # hulls.
Pulled tubing to 2460'. Pumped 80 sx cement w/300 # hulls.
Pulled tubing to 1200'. Pumped 80 sx cement w/300 # hulls. Cement to surface.
Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 25 sx cement. Casing full.
Connected to 8 5/8" surface casing. Pumped 45 sx cement. Maximum pressure 150 psi.

Perfs:

Top	Bot	Thru	Comments
3714	3716		
3710	3712		
3709	3712		
3657	3659		
3583	3587		
3581	3582		
3580	3581		
3570	3572		
3547	3549		
3530	3534		

Remarks: SWIFT SERVICES TICKET # 21912

Plugged through: TBG

RECEIVED

JUL 25 2012

KCC WICHITA

District: 04

Signed Darrel Dipman
7/16/12 (TECHNICIAN)

CM

JUL 17 2012