

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-06986-00-00
Spot: W2SWSW Sec/Twnshp/Rge: 25-14S-14W
660 feet from S Section Line, 4950 feet from E Section Line
Lease Name: BEN REIN Well #: 1
County: RUSSELL Total Vertical Depth: 3143 feet

Operator License No.: 30317
Op Name: J.H.R., INC.
Address: 533 WASHINGTON RD STE 100
BRIDGEVILLE, PA 15017

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5	3136		
SURF	8.625	251		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/10/2012 9:00 AM
Plug Co. License No.: 34147 Plug Co. Name: ACE WELL SERVICE, INC.
Proposal Revd. from: WARD CRAIG Company: J.H.R., INC Phone: (785) 483-1543

Proposed Plugging Method: Ordered 300 sx of 60/40 pozmix 4% gel cement w/300 # hulls and 9 sx gel.
Perforations: 300', 745' and 1250'.
Junk in well @ 2330' (bottom of head breaker). Drove Iron to 2330'.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/10/2012 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2320'. Pumped 50 sx cement ~~retained~~ w/100 # hulls.
Pulled tubing to 1250'. Pumped 125 sx cement.
Cement circulated.
POOH. Hooked to casing and pumped 15 sx cement @ 200 psi.
Pumped 30 sx cement down braden head until full.

Perfs:

Top	Bot	Thru	Comments
3136	3143		OHIO

Remarks: QUALITY CEMENTING TICKET #906

Plugged through: TBG

District: 04

Signed

Ray A Dinkel
7/10/12

(TECHNICIAN)

CM

RECEIVED
JUL 25 2012
KCC WICHITA

JUL 12 2012