

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21033-00-00
Spot: NESESW Sec/Twnshp/Rge: 18-12S-17W
834 feet from S Section Line, 3016 feet from E Section Line
Lease Name: LSCHMEIDLER Well #: 5
County: ELLIS Total Vertical Depth: 3740 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3739		125 SX
SURF	8.625	255		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/16/2012 12:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING Phone: (620) 938-2943

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement, 8 sx gel and 500 # hulls.
DV Tool-1323' w/400 sx cement.
Perforations: ARB-3654'-3662'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/16/2012 5:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Mike's Testing ran in hole with tubing to 3500'. Copeland rigged to tubing. Mixed and pumped 8 sx gel followed by 50 sx cement w/200 # hulls.
Pulled tubing to 1800'. Copeland rigged to tubing. Mixed and pumped 136 sx cement w/300 # hulls to circulate cement to pit area.
Pulled tubing. Topped off 4 1/2" casing w/12 sx cement. Hole standing full.
Rigged to 8 5/8" casing and pumped 8 sx cement to pressure with 200 psi. Shut in pressure 200 psi.


Remarks: COPELAND ACID AND CEMENTING CO TICKET # 39876

Plugged through: TBG

RECEIVED
JUL 25 2012
KCC WICHITA

District: 04

Signed


7/26/12 (TECHNICIAN)

CA

JUL 17 2012