

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20982-00-00
Spot: E2NESWNE Sec/Twnshp/Rge: 36-15S-13W
1650 feet from N Section Line, 1550 feet from E Section Line
Lease Name: SELLENS C Well #: 6
County: RUSSELL Total Vertical Depth: 3361 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3356		100 SX
SURF	8.625	554		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/13/2012 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: GRADY BOLDING Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 564-2240

Proposed
Plugging
Method:

Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls and 10 sx gel.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/13/2012 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1450'-840' and 430'.
Ran tubing to 3200'. Pumped 9 sx gel followed by 75 sx cement w/200 # hulls.
Pulled tubing to 1500'. Pumped 65 sx cement w/100 # hulls.
Pulled tubing to 850'. Pumped 65 sx cement w/100 # hulls.
Pulled tubing to 450'. Pumped 140 sx cement. Circulated cement out of casing and surface pipe. Pulled tubing. Topped off w/5 sx cement.

Perfs:

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG T86

RECEIVED
JUL 25 2012
KCC WICHITA

District: 04

Signed Bruce Rodie
7/26/12 (TECHNICIAN)

CM