

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19054-00-01
Spot: W2NESE Sec/Twnshp/Rge: 31-13S-14W
1980 feet from S Section Line, 990 feet from E Section Line
Lease Name: BROWN OWWO Well #: 5
County: RUSSELL Total Vertical Depth: 3341 feet

Operator License No.: 31341
Op Name: CRAIG, WARD DBA CRAIG OIL COMPA
Address: 15 S MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3329		150 SX
SURF	8.625	904		410 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/12/2012 7:45 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: WARD CRAIG Company: CRAIG OIL COMPANY Phone: (785) 483-1543

Proposed Plugging Method: Ordered 200 sx 60/40 pozmix 4% gel cement w/700 # hulls.
Junk in the well @ 825' (packer, tail pipe and 1 joint of tubing on top). Tried fishing out of well 3-5 days. Lost wash over pipe once. Fished wash over pipe out of well.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/12/2012 2:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 725'. Pumped 105 sx cemetn w/200 # hulls.
Had cement to surface but lost all circulation.
POOH. Waited on cement.
Ran tubing in and tagged cement. Pulled up to 325' and pumped 25 sx cement w/150 # hulls.
Cement circulated.
POOH. Topped off w/5 sx of cement.
Checked on. Filled up and down 1'.

Perfs:

Top	Bot	Thru	Comments
3320	3322		

Remarks: QUALITY CEMENTING TICKET # 703

Plugged through: TBG

RECEIVED
JUL 25 2012
KCC WICHITA

District: 04

Signed

Ray A. Dinkel
7/26/12

(TECHNICIAN)

CM