

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21305-00-00
Spot: SWSWNWSW Sec/Twnshp/Rge: 25-8S-30W
1567 feet from S Section Line, 140 feet from W Section Line
Lease Name: QUAKENBUSH UNIT Well #: 1
County: SHERIDAN Total Vertical Depth: 4000 feet

Operator License No.: 9860
Op Name: CASTLE RESOURCES, INC.
Address: BOX 87
SCHOENCHEN, KS 67667

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	250		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/18/2012 12:00 AM
Plug Co. License No.: 34743 Plug Co. Name: WHITE KNIGHT DRILLING LLC
Proposal Rcvd. from: DARRELL Company: WHITE KNIGHT DRILLING LLC Phone: (785) 567-6144

Proposed Plugging Method: Ordered 205 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 07/18/2012 8:30 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @2525 w/25 sx
2nd plug @1625 w/100 sx
3rd plug @300 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: SOS

Plugged through: DP

RECEIVED
JUL 25 2012
KCC WICHITA

District: 04

Signed [Signature]
(TECHNICIAN)

JUL 18 2012