

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25715-00-00
Spot: NWNWSENE Sec/Twnshp/Rge: 1-18S-14W
1598 feet from N Section Line, 1026 feet from E Section Line
Lease Name: BENTON Well #: 1-42
County: BARTON Total Vertical Depth: 3423 feet

Operator License No.: 34110
Op Name: CAERUS KANSAS LLC
Address: 600 17TH ST, STE 1600 N
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	829		325 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/10/2012 12:00 AM
Plug Co. License No.: 34233 Plug Co. Name: MAVERICK DRILLING LLC
Proposal Rcvd. from: _____ Company: JOSH Phone: (316) 262-6706

Proposed Plugging Method: Ordered 190 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DAVID WANN WitnessType: NONE
Date/Time Plugging Completed: 07/10/2012 12:00 AM KCC Agent: DAVID WANN

Actual Plugging Report:

1st plug @3341 w/25 sx
2nd plug @880 w/40 sx
3rd plug @300 w/70 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY OILWELL

Plugged through: DP

RECEIVED
JUL 25 2012
KCC WICHITA

District: 04

Signed [Signature]
7/26/12 (TECHNICIAN)

CM

JUL 18 2012