

To: 071085  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-21

API NUMBER 15-135-23,200-0000 139  
SW SW NW, SEC. 28, T. 19 S, R. 21 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3536

Operator: Ramco Energy Corporation  
Name & Address  
P.O. Box 340  
Great Bend, KS 67530

2970 feet from S section line  
4950 feet from E section line

Lease Name Lapka Well # 1  
County Ness 146.12

Well Total Depth 4496 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 612

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 2:40 p.m. Day: 21 Month: 8 Year: 19 92

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4495' w/150 sx cement, Perfs at 4440-42'

1st plug sand back to 4390' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 175 sx cement.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4 p.m. Day: 21 Month: 8 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4390' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 175 sx cement.

Maximum pressure 800 psi and shut in 400 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
08-25-1992  
AUG 25 1992

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2191' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

(I did / did not) observe this plugging.

Signed Dan Goodrow  
(TECHNICIAN)

DATE 8-27-92  
NO. 36063