

STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION SE NW SE SW, SEC. 31, T 19 S, R 21 W/K

130 S. Market, Room 2078
Wichita, KS 67202
766 feet from S section line
3406 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 4767
Lease Name Foos "A-P" Well # 2

Operator: Ritchie Exploration, Inc. County Ness 143.58
Name: Address 125 N. Market, Ste. 1000
Wichita, KS 67202
Well Total Depth 4418 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 512

Abandoned Oil Well X Gas Well Input Well SWD Well O&A
Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage License Number 31529
Address P.O. Box 209, Chase, KS 67524-0209

Company to plug at: Hour: 9:40 a.m. Day: 20 Month: 3 Year: 19 97
Plugging proposal received from James

(company name) Mike's Testing & Salvage (phone) 316-938-2943
were: 4 1/2" at 4405' w/75 sx cement, PBSD 4414', Open hole 4405-4414'

1st plug sand back to 4355' and dump 4 sx cement on top of sand through bailer,
2nd plug at Anhydrite with 50 sx cement, 3rd plug at 700' with 50 sx cement,
4th plug at 250' with 40 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None
Operations Completed: Hour: 12 p.m. Day: 20 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4355' and dumped 4 sx cement on top of sand through bailer,
2nd plug at 1490' with 50 sx cement and 100 lbs. hulls,
3rd plug at 700' with 40 sx cement and 100 lbs. hulls,
4th plug at 512' with 50 sx cement,
5th plug at 200' with 40 sx cement, 6th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied, recovered 1520' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observed this plugging
DATE 3-26-97
WV. NO. 47823
3-20
RECEIVED
Signed Michael J. Maier
(TECHNICIAN)
03-25-1997
FORM CP-2/3
Rev. 01-84