

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-21845-00-01  
Spot: CSENE Sec/Twnshp/Rge: 31-19S-21W  
2030 feet from N Section Line, 710 feet from E Section Line  
Lease/Unit Name: LYLE SCHABEN P Well Number: 1  
County: NESS Total Vertical Depth: 4400 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: BOX 783188 8100 E 22ND ST. N. #700  
WICHITA, KS 67278

Conductor Pipe: Size \_\_\_\_\_ feet: \$143.00  
Surface Casing: Size 8.625 feet: 505  
Production: Size 5.5 feet: 4390 WITH 100 SX CMT  
Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/25/2002 10:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4267' & 5 SX CMT. 1ST PLUG AT 1000' WITH 15 SX GEL - 40 SX CMT. 2ND PLUG AT 700' WITH 50 SX CMT. 3RD PLUG 580' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 02/27/2002 4:10 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4400'. PERFS AT 4381-90'. 02/25/2002: SAND TO 4267' & 4 SX CMT. CASING HAS HOLES IN IT AT ABOUT 1070' AND ANOTHER BELOW THAT. CASING WAS PARTED AT 835'. SHUT DOWN. 02/27/2002: RAN TUBING DOWN TO 925' AND COULDN'T GET ANY LOWER. 1ST PLUG AT 925' WITH 80 SX CMT WITH 400# HULLS. 2ND PLUG AT 525' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED  
MAR 13 2002  
KCC WICHITA  
03-13-2002

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 835' OF 5 1/2" CASING.

Plugged through: TBG

District: Q1

Signed Michael Maier  
(TECHNICIAN)

INVOICED  
DATE 3-14-02 MAR 08 2002  
VV. NO. 2002061526 MP

FORM C-1024