

15-135-20365-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Ness County, Sec. 14 Twp. 19S Rge. (E) 21(W)
Location as "NE/CNW/SW" or footage from lines C NE SE
Lease Owner Nadel & Gussman
Lease Name Boese Well No. 1
Office Address 1714 First Natl. Bldg., Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 3, 1970
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced September 3, 1970
Plugging completed September 3, 1970
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey of Hays
Producing formation Depth to top Bottom Total Depth of Well 4373 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	330'	8-5/8"	330'	-----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 600 Feet,
Plug and 40 sax Cement; Mud to 310 Feet,
Plug and 25 sax Cement; Mud to 40 Feet,
1/2 sax Halls and Plug bridged with Kelly
and 10 sax Cement to Base of Cellar;
2 sax Cement in Rat Hole. Job Completed
@ 10:30 P.M. by Allied Cementing Co.

RECEIVED
STATE CORPORATION COMMISSION

SEP 10 1970

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Allied Cementing Co.
Address Box 207, Russell, Kansas

09-10-1970

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
T. M. McCaul, Jr. of Sage Drilling Co. (employee of owner) of the above described well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.


(Signature)

500 Bitting Building, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 4th day of September, 1970

Louise K. Whitted
Notary Public.

November 26, 1970.



15-135-20365-00-00

DRILLERS LOGBOESE NO. 1

CASING RECORD:	OPERATOR:	Nadel & Gussman	DESCRIPTION:
8-5/8" @ 330'	CONTRACTOR:	Sage Drilling Co.	C NE SE
w/200 sax cement	COMMENCED:	August 26, 1970	Sec. 14-19S-21W
			Ness County, Kansas
TOTAL DEPTH:	COMPLETED:	September 3, 1970	ELEVATION: 2208KB
4373'			

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Rock	0	35	
Rock & Shale	35	332	
Clay	332	535	
Shale	535	615	
Red Bed	615	865	
Sand	865	1110	
Shale & Shells	1110	1339	
Shale	1339	1442	
Anhydrite	1442	1475	
Shale, Shells & Lime	1475	1802	
Shale & Lime	1802	2290	
Lime & Shale	2290	2805	
Shale & Lime	2805	3300	
Lime & Shale	3300	3479	
Shale & Lime	3479	3691	
Lime & Shale	3691	3768	
Lime	3768	3825	
Lime & Shale	3825	3940	
Lime	3940	4110	
Lime & Shale	4110	4202	
Lime	4202	4343	
Lime & Chert	4343	4373	D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., , INC.

By *Louise K. Whitted*



Subscribed and sworn to before me this 4th day of September, 1970.

My commission expires:
November 26, 1970.

RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1970
Louise K. Whitted, Notary Public
CONSERVATION DIVISION
Wichita, Kansas

09-10-1970