


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. 25 Twp. 19S Rge. (E) 21W (W)

Location as "NE/CNW/SW/" or footage from lines NW NE
Lease Owner Adair Oil Company
Lease Name ANTENEN Well No. 1
Office Address Box 7011, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-1 19 70
Application for plugging filed 2-1 19 70
Application for plugging approved 2-1 19 70
Plugging commenced 2-1 19 70
Plugging completed 2-1 19 70
Reason for abandonment of well or producing formation No oil or gas
found in commercial quantities.
If a producing well is abandoned, date of last production -- 19 --
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation None Depth to top Bottom Total Depth of Well 4445' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	250'	-0-
				RECEIVED STATE CORPORATION COMMISSION FEB 9 1970 CONSERVATION DIVISION Wichita, Kansas		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

02-09-1970

Mud to 600', cemented with 70 sacks. Mud to 240', cemented with 20 sacks. Solid bridge at 40', cemented with 10 sacks. Hole plugged at 10:30 A.M., 2-1-70.

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.
Address 1425 Wichita Plaza - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
1425 Wichita Plaza - Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 5 day of February 19 70

My commission expires 6-30-71 Sherry Gish Notary Public.

15-135-20317-00-00
ADAIR OIL COMPANY
P. O. Box 7011
Wichita, Kansas

Adair Oil Company &
J. E. Morris
Antenen #1
NW-NE
Section 25-19-21W
Ness County, Kansas
E1. 2279 K. B.

Comm: 1-23-70
Comp: 2-1-70
Contractor: Rains & Williamson
8 5/8 @ 245 w/175 SX
Pro: D & A

Figures indicate bottom of formations:

shale & lime	1504
anhydrite	1536
shale & lime	2500
lime	3788
shale	3807
lime	3817
shale	3835
lime	4200
shale & lime	4230
lime	4258
shale	4275
lime	4298
shale	4210
lime	4327
shale	4380
chert & shale	4421
chert	4447

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1970
CONSERVATION DIVISION
Wichita, Kansas

02-09-1970

Welex tops:

Anhydrite	1504	(+775)
Heebner	3788	(-1509)
Toronto	3807	(-1528)
Lansing	3835	(-1556)
Fort Scott	4310	(-2031)
Cherokee	4327	(-2048)
Cherty Conglomerate	4380	(-2102)
Mississippi	4421	(-2142)
T.O.	4447	

Sherrill Compton
Sherrill Compton
Geologist