

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-135-22320-00-00
API NUMBER Spud 10-30-82

LEASE NAME Meyer

WELL NUMBER 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 21 TWP. 19S RGE. 21W (E) or (W)

COUNTY Ness

Date Well Completed

Plugging Commenced 3-10-94

Plugging Completed 3-22-94

LEASE OPERATOR Joe Gerstner Oil Co.

ADDRESS RR #1, Box 115A Ness City, KS 67560

PHONE# (913) 798-2893 OPERATORS LICENSE NO. 9615

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 4440'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	568'	none
				4 1/2	4439'	2410'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from foot to foot each set.

Sanded bottom @ 3764' & dumped 4 sks cement. Shot @ 3000', worked pipe. Shot @ 2600', worked pipe. Shot @ 2410', came loose, pulled up to 1500'. Pumped 50 sks cement @ 1550'. Pulled up to 700', pumped 80 sks cement. Pulled up to 40', pumped 20 sks. Pulled rest of pipe. 60/40 poz 6% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Joe Gerstner Oil Co.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 24th day of March

Duane Gerstner
Notary Public

My Commission Expires:



15-135-22320-00-00

GREAT GUNS

Digital Log

R A Guard Log

FILE NO.	COMPANY	PETRO-VENTURES, INC.		
	WELL	MEYERS NO. 2		
	FIELD	SCHABCH		
	COUNTY	NEES	STATE	KANSAS
	LOCATION:	E/2-SW-SW		
	SEC	TWP	RGE	21W

OTHER SERVICE:

Permanent Datum GROUND LEVEL Elev 2275
 Log Measured from KELLY BUSHING 8 Ft. Above Permanent Datum
 Drilling Measured from KELLY BUSHING

Elevations
 KB 2283
 DF --
 GL 2275

Date	11-5-82			
Run No	ONE			
Depth—Driller	4440			
Depth—Logger	4438			
Bottom Logged Interval	4436			
Top Logged Interval	00			
Casing—Driller	8-5/8 @ 566	@	@	@
Casing—Logger	566			
Bit Size	7-7/8			
Type Fluid in Hole	DAPAC			
	25.000			
Density and Viscosity	9.6 53			
pH and Fluid Loss	12.0 110.4	cc		cc
Source of Sample	FLOW LINE			
Rm @ Meas Temp	26 @ 60°			
Rmf @ Meas Temp	20 @ 60°			
Rmc @ Meas Temp	.43 @ 60°			
Source of Rmf and Rmc	CHEPTON			
Rm @ BHT	14 @ 119°			
Time Since Circ.	2 HOURS			
Max Rec Temp Deg F	119°			
Equip No and Location	52 G.S.			
Recorder S.	GREYER			
Time Recorder E	ROLF ANDERSON			

RECEIVED
 STATE CORPORATION COMMISSION

NOV 04 1993

CONSERVATION DIVISION
 Wichita, Kansas