

15-135-20565-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plot

Ness County. Sec. 21 Twp. 9S Rge. 19 (E) 21 (W)
Location as "NE/CNW/SW" or footage from lines C SE SE
Lease Owner Acme Oil Corp.
Lease Name Meyer Well No. 1
Office Address 6235 W. Kellogg - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed 2-6-72 19
Application for plugging filed 2-6-72 19
Application for plugging approved 2-6-72 19
Plugging commenced 4:15 PM 2-6-72 19
Plugging completed 5:30 PM 2-6-72 19
Reason for abandonment of well or producing formation dry
If a producing well is abandoned, date of last production none 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3880 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	515	8 5/8	511	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug hole 50sx @ 720' 20 sx @ 420' and 10 sx @ 40'
2 sx in rat hole by Leo Massey & Allied.

RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1972
CONSERVATION DIVISION
Wichita, Kansas

02-10-1972

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor B & R Drilling, Inc.
Address 720 Union Center - Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bill Lahar (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Lahar
720 Union Center - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of February, 19 72

My commission expires May 31, 1974

Alma A. Neises
Notary Public.

15-135-20565-00-00

B & B DRILLING, INC.

~~2070 Petroleum Building~~ 720 UNION CENTER
Wichita, Kansas 67202

February 8, 1972

DRILLERS LOG

Re: Meyer #1
C SE SE Section 21-¹⁹28-21W
Ness County, Kansas

OPERATOR: Acme Oil Corp.
CONTRACTOR: B & B Drilling, Inc.
COMMENCED: January 31, 1972
COMPLETED: January 6, 1972
TOTAL DEPTH: 3830'

Set 8 5/3" @ 511' w/265sx

0	515	Surface Hole
515	1235	Shale & Sand
1235	1545	Shale & Sand
1545	1578	Anhydrite
1578	1760	Shale & Sand
1760	2250	Shale & Lime
2250	2421	Shale & Lime
2421	2620	Shale & Lime
2620	2760	Lime
2760	3112	Lime & Shale
3112	3260	Lime & Shale
3260	3535	Shale
3535	3675	Lime
3675	3880	Lime & Shale
3880		Total Depth

RECEIVED
STATE CORPORATION COMMISSION
FEB 10 1972
CONSERVATION DIVISION
Wichita, Kansas

02-10-1972

D & A

We certify the above and foregoing to
be true and correct copy of the log on
the #1 Meyer, located in Ness County,
Kansas.

Bill Laker President

Alma A. Neises Notary Public
Subscribed and sworn to before me this 9th
day of February, 1972.
My commission expires May 31, 1974