


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-135-00333-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Ness County, Sec. 21 Twp. 19S Rge. 21 (E) (W)  
Location as "NE/CNW/SW" or footage from lines C SW SW  
Lease Owner Ferguson Oil Company and Walters Drilling Co.  
Lease Name Meyer Well No. 1  
Office Address 522 Union Center Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 23 1963  
Application for plugging filed December 24 1963  
Application for plugging approved December 31 1963  
Plugging commenced January 7 1964  
Plugging completed January 7 1964  
Reason for abandonment of well or producing formation Dry  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4403 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippian	Oil & Water	4399	4403	5 1/2	4399'	3300'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.  
Set plug at 490' and ran 20 sacks of cement from 490' to 430'. Mudded from 430' to 200'. Ran 20 sacks of cement from 200' to 140'. Mudded from 140' to 30', and ran 10 sacks of cement from 30' to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 15 1964  
01-15-1964  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.  
Address Box 156, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
L. Wendell Knox (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. Wendell Knox Attorney-in-Fact for  
Ferguson Oil Company, 522 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of January, 1964

My commission expires September 5, 1967  
Betty Welch  
Betty Welch Notary Public.

cc: Walters Drilling Co.

DRILLER'S LOG

COMPANY: WALTERS DRILLING CO., &  
FERGUSON OIL CO., ET AL

WELL NAME: MEYER 'C' NO. 1  
C SW SW SEC. 21-19S-21W  
NESS COUNTY, KANSAS

CONTRACTOR: WALTERS DRILLING CO.  
510 ORPHEUM BUILDING  
WICHITA 2, KANSAS

ROTARY DRILLING COMMENCED: DECEMBER 6, 1963

ROTARY DRILLING COMPLETED: DECEMBER 19, 1963

ELEVATION: 2266 KB  
2263 DF  
2261 GL

CASING RECORD: 8 5/8" @ 490' w/ 275 sacks cement

LOG

0 - 20	Surface Clay
20 - 285	Shale
285 - 312	Shale
312 - 330	Sand
330 - 410	Shale-shells
410 - 435	Sand
435 - 565	Shale and Shells
565 - 775	Shale
775 - 900	Red Bed and Sand
900 - 1125	Sand
1125 - 1505	Shale
1505 - 1540	Anhydrite
1540 - 1595	Shells and Shale
1595 - 2185	Shale and Shells
2185 - 2770	Lime and Shale
2770 - 2850	Shale and Shells
2850 - 3100	Lime and Shale
3100 - 3285	Shale and Broken Lime
3285 - 3420	Shale
3420 - 3605	Lime and Shale
3605 - 3715	Shale, Lime and Shells
3715 - 3795	Shale and Lime
3795 - 3984	Lime
3984 - 4060	Lime and Shale
4060 - 4103	Lime
4103 - 4130	Lime and Shale
4130 - 4205	Shale and Lime Streaks
4205 - 4260	Shale and Lime
4260 - 4305	Lime
4305 - 4326	Shale and Lime
4326 - 4385	Shale, Lime and Chert
4385 - 4402	Lime and Chert
<u>4402</u>	<u>Rotary Total Depth</u>

RECEIVED  
STATE CORPORATION COMMISSION

DEC 31 1963  
12-31-1963  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, Robert F. Walters, hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.


WALTERS DRILLING CO.

ROBERT F. WALTERS, Partner

STATE OF KANSAS )  
                  ) SS.  
COUNTY OF SEDGWICK)

BE IT REMEMBERED that, on this 26th day of December, 1963, before me, the undersigned, a Notary Public duly commissioned in and for the State and County aforesaid, came Robert F. Walters, known to me to be the same person who executed the foregoing instrument as Partner and in behalf of the Walters Drilling Co. and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.



My Commission Expires:

October 4, 1967

*Juanita M. Green*

Juanita M. Green, Notary Public