


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-135-00126-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County. Sec. 26 Twp. 19S Rge. 21 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines SW SW NW
Lease Owner Aurora Gasoline Company, Etal
Lease Name Antanen Well No. 1
Office Address 1107 Union National Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed Sept. 1 1957
Application for plugging filed " 19 " "
Application for plugging approved " 19 " "
Plugging commenced " 19 " "
Plugging completed " 19 " "
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage, Box 283, Hoisington, Kansas
Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 4430 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	0	516	8 5/8"	511.44	None
See Attached Log						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud from 4430 to 1100': Dumped 40 Sacks of cement on Bridge Plug at 1100';

Filled with Mud to 480': Dumped 20 Sacks of cement on Bridge at 480';

Filled with mud to 35': Dumped 5 Sacks of cement on Bridge Plug at 35';

Filled to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rex & Morris Drilling Company
Address Box 334, El Dorado, Kansas

STATE OF Kansas COUNTY OF Butler, ss.
G. E. McClure

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. E. McClure
Box 334, El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of September, 1957

My commission expires July 23, 1960

Winifred E. Cruit
Winifred E. Cruit Notary Public.

PLUGGING
FILE SEC 26 T 19 L 21W
BOOK PAGE 42 LINE 11

09-19-1957

15-135-00126-00-00

Elevation 2242 FT
2243 FT

ANTENEN # 1

AURORA GASOLINE CO. BT AL

Total Depth - 4430
Contractor - Rex & Merrid Drilling Co.
Commenced - 8-21-57
Completed - 9-1-57
Initial Production - D & A

Location - SW-SW NW
Section - 26-19S-21W
North County, Kansas

Geology Record:
6-5/8 @ 311.44 w/ 324 sacks

FORMATION

DEPTH

Surface Hole	516
Shale & Shells	1470
Ashy shale	1505
Shale	1575
Shale & Shells	1854
Shale & Lime	2215
Lime & Shale	3443
Shale & Lime	3565
Shale & Shale	3765
Shale & Lime	3855
Lime	4183
Lime & Shale	4215
Shale & Lime	4365
Shale & Shale	4420
Shale & Lime	4345
Cherty Lime	4430

T.D.

Ran Millington Guard Log

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Rex & Merrid Drilling Company

By Paul J. Merrid

Title Geologist

STATE OF KANSAS)
COUNTY OF BUTLER) SS.

Subscribed and sworn to before me, a Notary Public, this 11th day of September 1957.

Winifred E. Pruitt
Winifred E. Pruitt - Notary Public

My commission expires:

July 23, 1960.

RECEIVED
STATE REGISTRATION COMMISSION
SEP 19 1957
09-19-1957
REGISTRATION DIVISION
Topeka, Kansas

PLUGGING
FILE SEC 21a T. 19 R. 21W
BOOK PAGE 42 LINE 11