

15-135-21995-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ness SEC. 28 TWP. 19 RGE. 21 E/W
Location as in quarters or footage from lines:
NW NE NW

Locate Well
correctly on above
Section Platt.

Lease Owner Petroventures Inc.
Lease Name Rein Well No. 1
Office Address Suite 600 4704 Harlan St. Denver Col. 80212
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 4-17-81
Application for plugging filed 4-17-81
Plugging commenced 4-17-81
Plugging completed 4-17-81
Reason for abandonment of well or producing formation No show
on DST or Electric Logs

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation N/A Depth to top _____ bottom _____ T.D. 4555

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

- Plug #1 Spot 60 sx. class A 50/50 Poz mix @ 1000 ft. to 750 ft. with open ended drill pipe
 - Plug #2 Spot 30 sx. class A 50/50 Poz mix @ 330 ft. to 215 ft. with open ended drill pipe
 - Plug #3 Insert LA-10 wooden plug to 40 ft. fill 20 ft. up with drilling mud. Top off with 5 sx. class A 50/50 Poz mix
- Rat and Mouse holes filled with 5 sx. each of 50/50 Poz mix.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton

RECEIVED
STATE CORPORATION COMMISSION
05-28-81
MAY 28 1981
CONSERVATION DIVISION
Wichita, Kansas


STATE OF Kansas COUNTY OF Ellis, ss.
James Huddleston (employee of owner) or (owner or operator) of the

above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) James Huddleston
Box 1193 Hays, Ks. 67601
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of May, 19 81

My Commission expires:



Cynthia A. Dreiling
Notary Public

15-135-21995-00-00

Operator Petroventures (1979) LTD		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Rein	DRY HOLE
S 28 T 19 R 21 W NW NE NW		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Samples or drilling time did not warrant a drill stem test.			ANHYDRITE	1454
			HEEBNER	3820
			LANSING	3864
			PAWNEE	4296
			FT. SCOTT	4361
			CHEROKEE	4376
			MISSISSIPPI (chat)	4474
			LOG T.D.	4555

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD

RECEIVED
STATE CORPORATION COMMISSION
MAY 28 1981
CONSERVATION DIVISION
Topeka, Kansas

Date Received	Signature
	Title
	Date