

15-135-20826-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Ness County, Sec. 33 Twp. 19S Rge. (E) 21W  
Location as "NE/CNW/SE" or footage from lines C N/2 SE NE  
Lease Owner The National Oil Company, Inc.  
Lease Name Ely Well No. 1  
Office Address 200 W. Douglas, Suite 550, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 12-9-73  
Application for plugging filed 12-9 19 73  
Application for plugging approved 12-9 19 73  
Plugging commenced 12-9 19 73  
Plugging completed 12-9 19 73  
Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4465 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Fluid	Surface	398	8-5/8"	390'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fluid to 720, plug, 70 sx cement;  
Fluid to 240, plug, 20 sx cement, 1/2 sx hulls;  
Fluid to 40, plug, 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 17 1973  
CONSERVATION DIVISION  
Wichita, Kansas  
12-17-1973

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor D N B DRILLING, INC.  
Address 701 First Nat'l Bldg., Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF \_\_\_\_\_ ss.  
JAMES L. DONELSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson  
701 First Nat'l Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of December 19 73

Ella Priess  
Notary Public.

My commission expires August 25, 1976

Ella Priess  
STATE NOTARY PUBLIC  
Sedgwick County, Kansas  
My Com. Expires Aug. 25, 1976

15-135-20826-00-00

DRILLERS' LOG

NATIONAL OIL COMPANY  
No. 1 Ely  
C N/2 SE NE, Sec. 33-19S-21W  
Ness County, Kansas

Elev: 2290 K.B.

Commenced: 11-27-73  
Completed: 12-9-73

Surface Casing: 390' of 8-5/8"  
casing cemented w/225 sx cement,  
3% cc. 11-28-73

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 398
Shale & Sand	398 - 950
Sand	950 - 1140
Shale	1140 - 1235
Red Bed	1235 - 1511
Anhydrite	1511 - 1544
Shale	1544 - 2090
Shale & Lime	2090 - 2305
Lime & Shale	2305 - 3850
Lime	3850 - 4465 T.D.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 17 1973  
CONSERVATION DIVISION  
Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

*James L. Donelson*  
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 14th day of December 1973.

My Commission Expires:  
August 25, 1976

*Ella Priess*  
Ella Priess, Notary Public

*Ella Priess*  
STATE NOTARY PUBLIC  
Sedgwick County, Kansas  
My Com. Expires Aug. 25, 1976