

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-23,200-00-00

LEASE NAME Lapka

WELL NUMBER 1

         Ft. from S Section LI

         Ft. from E Section LI

SEC. 28 TWP. 19 RGE. 21 XXXor (W)

COUNTY Ness

Date Well Completed         

Plugging Commenced 8-21-92

Plugging Completed 3:45 PM

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Ramco Energy Corp.

ADDRESS Box 340, Great Bend, Kansas 67530

PHONE# (316)792-1960 OPERATORS LICENSE NO. 3536

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-21-92 (date)

by Dan Goodrow (KCC District Agent's Name)

Is ACO-1 filled? Yes If not, Is well log attached?         

Producing Formation          Depth to Top 4440 Bottom 4442 T.O. 4496

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	612	0
				5 1/2	4495	2191

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from          feet to          feet each  
Bottom plug: Sanded to 4390 & bailed 5 sx cement..

Top plug: Pumped 300 lb Halls, 10 sx Gel, 50 sx Cement, 10 sx Gel, 100 lb Halls, 175 sx Cement. (60/40 w/6% gel). Had maximum pressure of 800 lbs & shut in of 400 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ramco Energy Corp.

STATE OF Kansas COUNTY OF Barton, ss.

Gary G. Burke


(Employee of Operator         )

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts the fe statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Gary G. Burke

(Address) Box 251, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 24 day of August, 19 92



Anna K. Burke  
Notary Public

My Commission Expires: 4-30-96

RECEIVED  
STATE CORPORATION COMMISSION  
08-25-1992  
AUG 25 1992

CONSERVATION DEPARTMENT  
WICHA OF KANSAS