

RRP

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

15-115-19255-0000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock

Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company

Complete Address: 1130 Wichita Plaza, Wichita, Kansas 67202

Lease Name Schick Well No. # 8

Location NE NW NW Sec. 33 Twp. 17 Rge. 4 (E) 991

County Marion Total Depth 2419'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling Company

Address: Great Bend, Kansas License No. # 399

Operation Completed: Hour 4 PM Day 28 Month 10 Year 69

The Above well was plugged as follows:

8 5/8"-107'-Circulated w/cement. 5 1/2"-2406'-Cemented. Sand hole to 2400'.

5 Sax.cement 2400' to 2360'. Mud 2360' to 120'. Bridge 120' to 110'.

25 Sax.cement 110' to 50'. Mud 50' to 40'. Bridge 40' to 30'.

10 Sax.cement 30' to 0. Pulled 1762'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

Signed: Highsmith
Well Plugging Supervisor

10-30-69
353-E