

15-135-20212-0000

Form CP-3

Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 6 - 68  
1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Mull Drilling Co., Inc.

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Harkness Well No. 1

Location C SW NW Sec. 4 Twp. 17 Rge. 23 (E) (W) X

County Neos Total Depth 4470

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Rains & Williamson Oil Co.

Address: Wichita, Kansas License No.     

Operation Completed: Hour 6:30A Day 5 Month 12 Year 1968

The Above well was plugged as follows:

RTD 4470' 8 5/8 csg set at 246' cwc 160 sc. Cmt. Mat. 50-50 poz cmt. W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cmt.  
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/6/68

INV. NO. 8957-4

Signed: Robert M. Massie  
Well Plugging Supervisor