

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Ks. 67202

API Number 15 -125-21,880<sup>-0000</sup> (of this well)

Operator's Full Name PALOMINO PETROLEUM.

Complete Address 500 INSURANCE BLDG. WICHITA, KS. 67202

Lease Name HARKNESS Well No. "K" - 51

Location Q-E 1/2 - SW - SE Sec. 5 Twp. 17 Rge. 23 (E) (W) W

County NESS Total Depth 4510 FT.

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D&A X

Other well as hereafter indicated     

Plugging Contractor STRATA DRILLING, CO.

Address 5619 - 8<sup>th</sup> ST. BOX 355 GREAT BEND, KS. License No.     

Operation Completed: Hour 8:00<sup>PM</sup> Day 17 Month SEPT Year 1980

The Above well was plugged as follows:

8 5/8" 279<sup>EF</sup> SP. CMC w/180<sup>SE</sup> COMMON-2% GEL. 3% PH-CL.  
ORDERED 110<sup>SE</sup> 50/50 PZMIX 6% GEL. + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1<sup>SE</sup> PLUG. @ 1100 FT w/ 70<sup>SE</sup> CMT.

2<sup>ND</sup> PLUG. @ 270 FT w/ 25<sup>SE</sup> CMT.

3<sup>RD</sup> PLUG. → SOLID BRIDGE HULL'S - PLUG @ 40<sup>EF</sup> to 0 w/ 10<sup>SE</sup> CMT.

3<sup>SE</sup> IN RAT HOLE.

2<sup>SE</sup> IN MOUSE HOLE. CEMENTED BY HALLIBURTON

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 9-24-80  
INVOICE NO. 32152

RECEIVED  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS  
CONSERVATION DIVISION  
9-22-80