

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 23 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Mill Drlg. Co. Inc.

Complete Address: 1625 Wichita Plaza Wichita, Kansas

Lease Name Albers Well No. 1

Location C SW/4 SE/4 Sec. 8 Twp. 17 Rge. 23 (E) (W) XX

County Ness Total Depth 4527

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Rains & Williamson

Address: Wichita, Kansas License No.     

Operation Completed: Hour 10:30P Day 18 Month 12 Year 1968

The Above well was plugged as follows:

RTD 4525' 8 5/8 csg set at 250' cwc. Cmt. Mat. 50-50 poz cmt. W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cmt.  
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INDEXED  
DATE 12-23-68  
INV. NO. 9085-W

Signed: Reo F. Massey  
Well Plugging Supervisor