

15735-76762-0000

Form CP-3
Rev. 6-4-68

~~KANSAS~~

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

MAR 7 1975
3-7-75
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Leben Oil Operations
Complete Address 1555 East Second, Wichita, Kansas 67214
Lease Name Oppliger Well No. 1
Location C NE SW Sec. 17 Twp. 17 Rge. (E) (W) 23
County Ness Total Depth 4440'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Kelso Pipe Pulling
Address Box 176, Chase, Kansas 67524 License No. 683
Operation Completed: Hour 2:30 P Day 5 Month 3 Year 1975

The above well was plugged as follows:

Total Depth 4440' 8 5/8 csg set at 288' cwc 225 sk.

5 1/2 csg set 4408' cw 150 sk cem.

Filled 5 1/2 csg W/sd (4440'-4390') dumped 4 sk cem W/dump bailer. (4390-4360)

Cutoff & recovered 3305' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg with 25 sk gel & water -100 lbs hulls -70 sk cem. -

5 sk gel & water -released plug & 50 sk cmt to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 3/11/75

INV. NO. 965-W