

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 4 1965  
3-4-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Mull Drg Co  
Complete Address: 1625 Wichita Plaza Wichita, Kans  
Lease Name Oppliger Well No. 2  
Location CSE SW Sec. 17 Twp. 17 Rge. (E) (W) 23  
County Ness Total Depth 4440  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated: \_\_\_\_\_  
Plugging Contractor: Globe Cementing Co  
Address: Great Bend, Kansas License No. \_\_\_\_\_  
Operation Completed: Hour 3:30PM Day 1 Month 3 Year 65

The Above well was plugged as follows:

8 5/8" 251' circulated with cement - 4 1/2" 4435' with 1/5 sax cement - DV collar at 1746' circulated hole from 1746' to 0' with 5/1 sax cement. no pipe recovery.

Pumped hole full heavy gel mud at 1200# pump pressure - pumped wiper plug followed by 60 sax cement at 1500# pump pressure - cement 120' to 0'

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

DATE 3/4/65  
REV. NO. 761-W

Signed: Eason Petty  
Well Plugging Supervisor